



Automated Startup and Commissioning Tests at ALS

Thorsten Hellert

Outline

- **Introduction**
 - Overview of Advanced Light Source Upgrade Project
 - Integration of SC Toolkit into ALS Control System
- **Commissioning Tests at ALS**
 - First turn threading
 - Pseudo-orbit correction
 - Turn-by-turn BBA

Design Choice of the Advanced Light Source Upgrade

- **Goal: Diffraction Limited Light Source**

- Brightness increase: $B_{ALS} = 2 \cdot 10^{19} \Rightarrow B_{ALSU} = 2 \cdot 10^{21}$
- Emittance decrease: $\epsilon_{ALS} = 2000 \text{ pm} \Rightarrow \epsilon_{ALSU} \sim 100 \text{ pm}$

- **Space Constraint**

- Use of current building and 12-fold symmetry

- **Requires Strong Focusing Elements**

- Quadrupole strength: $K_{ALS} \sim 3 \Rightarrow K_{ALSU} \sim 15$
- Sextupole strength: $M_{ALS} \sim 90 \Rightarrow M_{ALSU} \sim 800$

- **Requires Small Aperture**



- Magnet aperture: $d_{ALS} = 65 \text{ mm} \Rightarrow d_{ALSU} = 40 \text{ mm}$
- Undulator aperture: $d_{ALS} = 30 \text{ mm} \Rightarrow d_{ALSU} = 6 \text{ mm}$

- **Requires on-Axis Swap Out**


- Dynamic aperture: $DA_{ALS} = 120 \text{ mm}^2 \Rightarrow DA_{ALSU} = 3 \text{ mm}^2$

- **Requires Accumulator Ring**

- Injected beam: $\sigma_{ALS} = 2 \text{ mm} \Rightarrow \sigma_{ALSU} = 60 \mu\text{m}$



Overview of ALS-U Accelerator Facility




Limited Accessibility of Machine Properties

Power supplies



Operating machine



High level controls




Dagnostic devices
→

Magnetic fields
Particle trajectories
Magnet offsets
...

Limited access!

Setpoints and read back values

Realistic Workflow of Toolkit Important



Set Quad to setpoint

- Compensates bending angle difference by setting horizontal CM
- Checks for CM range (clipping)

Calculate fields

- Calibration errors of all components
- Includes dipole kick from bending angle (set-point & roll)

Auxiliary structures

- Diagnostic errors
- Injected beam trajectory
- Injection pattern

Get BPM reading



- Performs tracking including aperture
- Gets BPM signal from ensemble of particle trajectories

High level

- High level functions use only BPM and setpoints as input
- High level functions write only setpoints


Automated Startup and Commissioning Tests at ALS

- Automated startup and commissioning scripts will be essential for ALS-U
 - Lattice too non-linear to achieve stored beam with conventional methods
 - Scheduled commissioning time for AR and SR very short compared to the operational complexities
- SC Toolkit developed for simulated commissioning and error analysis studies
 - Comprehensive automated lattice correction tools to get from first injection to stored beam
 - Workflow mimics machine operation from the control room



Automated Startup and Commissioning Tests at ALS

- Automated startup and commissioning scripts will be essential for ALS-U
 - Lattice too non-linear to achieve stored beam with conventional methods
 - Scheduled commissioning time for AR and SR very short compared to the operational complexities
- SC Toolkit developed for simulated commissioning and error analysis studies
 - Comprehensive automated lattice correction tools to get from first injection to stored beam
 - Workflow mimics machine operation from the control room
- Integrating SC Toolkit into the control system
 - ALS and ALS-U operated with MML, toolkit written in Matlab
 - ALS lattice very similar to ALS-U AR lattice




Commissioning Tests at ALS



BPM Sum Signal Normalisation


- **Reliable BPM Sum Signal Key for First Turn Threading**
 - Beam loss detection is very important during early commissioning
 - Turn by turn BPM sum signal provides best path for beam loss detection
- **Large Shot-to-Shot and BPM-to-BPM Sum Signal Variation**
 - Variation of BPM first turn sum signal over 50 injections and all BPMs is 400% with no beam losses
- **BPM Sum Signal Calibration Procedure:**
 - 1) use first storage ring BPM to normalize all sum signals with injected bunch charge
 - 2) calculate BPM sensitivity by averaging over many nominal injections and save into file
- **Satisfactory Sum Signal Homogeneity:**
 - Final sum signal variation below 10%
 - Sufficient for accurate beam loss detection



First Turn Threading


- First Turn Threading at ALS-U:
 - Commissioning simulations show that automated first turn threading algorithm needed to reliably perform regular start up in the storage ring

First Turn Threading in Commissioning Simulation at ALSU-SR



First Turn Threading

- **First Turn Threading at ALS-U:**
 - Commissioning simulations show that automated first turn threading algorithm needed to reliably perform regular start up in the storage ring
- **Off Axis Injection at ALS**
 - ALS-U AR/SR commissioning will be done using on-axis injection
 - On axis injection at ALS not possible, thus injected beam trajectory must be corrected towards reference trajectory
 - Reference trajectory recorded during nominal injection
- **First Turn Threading Test:**
 - Add random CM excitations with 3mrad amplitude
 - Threading algorithm reliably restores reference injected beam trajectory




Achieving Stored Beam

- Pseudo-Orbit Correction

- The orbit BPM readings can be reliably calculated by averaging the BPM turn-by-turn data over >10 turns
- For off-axis injection a reliable way to achieve stored beam from multi-turn transmission is to correct the pseudo-orbit



- Pseudo Orbit Correction Test:

- Add random CM excitations with 1mrad amplitude
- Calculate orbit from turn-by-turn BPM readings taking 50 turns into account
- Pseudo orbit correction reliably restores initial orbit



Turn-by-Turn Beam Based Alignment

- Turn-by-Turn BBA Required for ALS-U
 - Commissioning simulations for ALS-U Storage Ring show that without $\sim 100\mu\text{m}$ rms BPM offsets reliable beam capture can not be expected
 - Initial BPM offsets to be expected at $\sim 500\mu\text{m}$ rms
 - Turn by turn BBA routine mandatory for successful beam capture at ALS-U SR




Turn-by-Turn Beam Based Alignment

- Turn-by-Turn BBA Required for ALS-U

- Commissioning simulations for ALS-U Storage Ring show that without $\sim 100\mu\text{m}$ rms BPM offsets reliable beam capture can not be expected
- Initial BPM offsets to be expected at $\sim 500\mu\text{m}$ rms
- Turn by turn BBA routine mandatory for successful beam capture at ALS-U SR

- TBT BBA Test:

- Algorithm was tested successfully before summer shutdown




Turn-by-Turn Beam Based Alignment

- Turn-by-Turn BBA Required for ALS-U

- Commissioning simulations for ALS-U Storage Ring show that without $\sim 100\mu\text{m}$ rms BPM offsets reliable beam capture can not be expected
- Initial BPM offsets to be expected at $\sim 500\mu\text{m}$ rms
- Turn by turn BBA routine mandatory for successful beam capture at ALS-U SR

- TBT BBA Test:


- Algorithm was tested successfully before summer shutdown
- Found offset was within $40\mu\text{m}$ of the one determined by stored beam BBA



MOPM010, IPAC'23


GUI Development Underway

- Focus on Accessibility
 - Graphical user interface crucial for easy access to turn by turn tools
 - Operator level desirable
- GUI Development:
 - First prototype of turn by turn GUI available and to be tested in upcoming physics shifts
 - Due to significant delays during latest startup no further studies have been possible



GUI Development Underway

- Focus on Accessibility
 - Graphical user interface crucial for easy access to turn by turn tools
 - Operator level desirable
- GUI Development:
 - First prototype of turn by turn GUI available and to be tested in upcoming physics shifts
 - Due to significant delays during latest startup no further studies have been possible



Summary and Conclusion

- **Advanced Light Source Upgrade**
 - 9 bend achromat lattice with 70pm-rad emittance
 - Very fast commissioning process required
- **Commissioning Tests at ALS**
 - Integration of SC toolkit into ALS control system underway
 - First turn threading, pseudo-orbit correction and turn-by-turn BBA successfully demonstrated at ALS
 - GUI development for easy accessibility underway